



European Agency for Safety and Health at Work





ISHCCO

International Safety & Health Construction Co-ordinator's Organisation

www.ishcco.org Forum da Vinci, 4-6 Bd. Grande Duchesse Charlotte L-1330 LUXEMBOURG













Communicating Risks to Constructors

Philip Baker



ISHCCO

01/12/2019 2



Communicating



Image courtesy of Shutterstock













12/1/2019

4



What Information?

- About risks in construction work:
 - -Now
 - In the future







Article 5

Project preparation stage: duties of coordinators

The coordinator(s) for safety and health matters during the project preparation stage appointed in accordance with Article 3 (1) shall:

(b) draw up, or cause to be drawn up, a safety and health plan setting out the rules applicable to the construction site concerned, taking into account where necessary the industrial activities taking place on the site; this plan must also include specific measures concerning work which falls within one or more of the categories of Annex II; VISION ZEROCO ISHCCO 12/1/2019 6

Safety and Health Plan

- 1. General information about the project
- 2. Project-specific information and information sources
- 3. Information on how the project should be managed
- 4. Arrangements for contributing information to the safety and health file













1. General information about the project

Description of the project

Names of the stakeholders

Client expectations on how the project will be carried out and the safety and health success criteria that will be applied

2. Project-specific information and information sources

Identifying project hazards

Identifying off-site hazards that will need to be taken into account

Identifying risks from the design that are not likely to be obvious to others (including the unusual)

Identifying work involving particular risks according to Annex II

Identifying other sources of information relevant to safety and health

3. Information on how the project should be managed

Management arrangements

Arrangements for welfare

Site rules (taking account as necessary of other industrial activities at the site)

Arrangements made to deal with common issues that are not likely to be obvious to others (including the unusual)

Arrangements made to take account of work involving particular risks

Arrangements made to take account of other activities at the site including industrial ones

Arrangements for safety and health during any joint occupation with the client and eventual handover to them

Arrangements in the event of injuries and emergencies

4. Arrangements for contributing information for the safety and health file





9



- UK
- Moved from Safety and Health Plan to Pre Construction Information in 2007
- SHCC Preparation Stage (UK) has less input on management of the works
- Since 2015 SHCC Preparation Stage (UK) is preferred to be the Lead Designer (Architect).





PtD Register

Designers' hazard elimination and management record											
Complete in Conjunction with guidance in PM/106/02								Mott MacDonald			
Project Title				Project Number				Project Manager			
RIBA Stage 3 to 4 for extension of the Northern Line, including 2 new stations and shafts				333592				R. Dickson			
				Division or Sub-Division				Project Safety Advisor			
				M&C				A. Harper			
Scope of Detailed design for new Battersea underground station							Form No/ Revision MMD-N001-2380000-HSE-RGT-00001				
(1) Haz Ref	(2) Activity:Process/ Material/Element - what is being undertaken?	(3) Hazard ⁴	(4) Stage of Work	(5) Package of Work	(6) Discipline	(7) Designer Risk Control Measures ² : Design action taken, record of decision process including option considered, design constraints and justification for options/actions not having been taken	(8) is there a 'significant' residual risk to be passed on? ³ (Y/N)	(9) If answer to (8) Is Yes, Information flow: D/P/F ⁴	(10) Status Within MM (Active / Closed)	Comments	
CONSTRUCTION											
BAT-C-002	Excavation and piling.	Munitions or unexploded ordnance present or likely to be present on site.	Construction		Geotechnical	 EOD Desktop UXO survey - EOD/13/13108/DTS/Northern Line Extension Identifies Battersea as high risk. FLO to consider commissioning on-site UXO survey to determine extent of any UXO and further mitigation. FLO to implement emergency plan to reflect risk and control measures in accordance with EOD Desktop Study. 	Yes	D		Please refer to EOD Explosive Ordnance Desk Top Study For Northern Line Extension (EOD13/13108/DTS/Northern Line Extension.	







Communicating









Article 5

Project preparation stage: duties of coordinators

The coordinator(s) for safety and health matters during the project preparation stage appointed in accordance with Article 3 (1) shall:

(c) prepare a file appropriate to the characteristics of the project containing relevant safety and health information to be taken into account during any subsequent works.



Safety and Health File

Introduction

- 1. General information about the project
- 2. Project-specific information and information sources
- 3. Information on how designers took account of hazards that might arise
- 4. Identifying other sources of information relevant to safety and health

From Non Binding Guide

Safety and Health File

Introduction

ISHCCO

1. General information about the project

Description of the project

Names of past stakeholders

2. Project-specific information and information sources

Identifying hazards

Identifying hazards from the design

Identifying high-risk hazards (Annex II)

3. Information on how designers took account of hazards that might arise during future construction work

Routine maintenance

More major work

4. Identifying other sources of information relevant to safety and health

VISION ZEROCO

ISHCCO



Plant Replacement

- Fan replacement strategy
- Shafts provided to ground level
- Lifting beams in place
- Blanking plates for isolating 'open' air path
- Loading points at ground level





Platform Edge Lighting





ISHCCO







Acknowledgment

Thank you for your attention.

Questions? Suggestions!

ISHCCO

